BRUHAT BENGALOORE MAHANARA PALIKE,YELAHANKA ZONE

BYATARAYANAPURA DIVISION

SCHEDULE-B (As Per Negotiated)

BBMP/2015-16/OW/WORK_INDENT18483/CALL-2

Earthwork and other Works for Temporary Immersion Tank for Lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB Overhead Tank in Ward No. 9, Vidyaranyapura Sub Division. (for 2016-17 year)

Sl. No.	Description	Item Code	Unit	Qty	Sanctioned Estimate		Rates Quoted Before R CHIDANANDA		Rates Quoted After R CHIDANANDA	
					Rate	Amount	Rate	Amount	Rate	Amount
1	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings,	1	Cum	42	156.88	6588.96	160.0	**6720.00**	160.0	**6720.00**
2	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in	2	Cum	214.5	188.68	40471.86	188.0	**40326.00**	188.0	**40326.00**
3	Above 1.5 Mtrs Depth Add 25% Extra	2a	Cum	214.5	235.86	50591.97	235.86	**50591.97**	235.86	**50591.97**
4	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	3	Sqm	820	6	4920	6.0	**4920.00**	6.0	**4920.00**
5	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the	4	Each	165	360	59400	375.0	**61875.00**	375.0	**61875.00**
6	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal	5	Cum	12.5	750	9375	750.0	**9375.00**	750.0	**9375.00**
7	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in	6	Hr	66	50	3300	50.0	**3300.00**	50.0	**3300.00**
8	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe	7	Days	165	244.55	40350.75	245.0	**40425.00**	245.0	**40425.00**
9	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed	8	Mtrs	480	65	31200	65.0	**31200.00**	65.0	**31200.00**
10	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft =	9	Sft	13200	8	105600	9.75	**128700.00**	9.75	**128700.00**
11	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of	10	Rft	165	17	2805	17.0	**2805.00**	17.0	**2805.00**
12	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	11	Nos	220	4	880	4.0	**880.00**	4.0	**880.00**
13	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the	12	Nos	110	40	4400	40.0	**4400.00**	40.0	**4400.00**
14	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining	13	Mtrs	1100	9	9900	9.0	**9900.00**	9.0	**9900.00**

[Providing erecting removing casurinapole barricading using]

Sl. No.	Description	Item Code	Unit	Qty	Sanctioned Estimate		Rates Quoted Before R CHIDANANDA		Rates Quoted After R CHIDANANDA	
					Rate	Amount	Rate	Amount	Rate	Amount
15	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per	14	Hr	66	562	37092	562.0	**37092.00**	562.0	**37092.00**
16	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per	15	Nos	88	285	25080	285.0	**25080.00**	285.0	**25080.00**
17	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in	16	Day	10	4000	40000	4000.0	**40000.00**	4000.0	**40000.00**
18	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by	17	Cum	357.5	77.76	27799.2	77.76	**27799.20**	75	**26812.50**
						499754.74		**525389.17**		**524402.47**
							R CHIDANANDA		**R CHIDANANDA**	
							525389.17	**499754.74**	**524402.47**	**-499754.74**
				Over Sanctioned Rates			**25634.43**	**5.13%**	**24647.73**	**4.93%**
							499754.74		**499754.74**	

The Lowest Rates Quoted by bidder R CHIDANANDA for +4.93% Above the Sanctioned Estimate rates is recommended for your kind Approval.

28/07

Assistant Engineer
Byatarayanapura Division

Executive Engineer 28/7/16.
Byatarayanapura Division

	Providing erecting removing casurinapole barricading using				

BRUHAT BANGALORE MAHANAGARA PALIKE

3MP/2015-16/OW/WORK_INDENT18483/CALL

NEGOTIATION SCHEDULE - B

Earthwork and other Works for Temporary Immersion Tank for Lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB Overhead Tank in Ward No. 9, Vidyaranyapura Sub Division. (for 2016-17 year)

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of R CHIDANANDA	
				In Figures	In Words
1	42	Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed etc complete as per specifications and directions of engineer in charge of the work	Cum	160	Rupees one hundred sixty only
2	214.5	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	188	Rupees one hundred Eighty Eight only
3	214.5	Above 1.5 Mtrs Depth Add 25% Extra	Cum	235.86	Rupees ~~Two Hundred Thirty five & Eighty~~ Six only
4	820	Code 0516 - Providing Plastic Sheet etc complete as per specifications and directions of engineer in charge of the work	Sqm	6	Rupees Six Only
5	165	Supply of water Through water Tank for filling Tank etc complete as per specifications and directions of engineer in charge of the work	Each	375	Rupees Three hundred Seventy five only
6	12.5	Providing Stone dust to approach road and near immersion tank for levelling and to protect not to sliping Sl No. 50 Code 400 metal Component etc complete as per specifications and directions of engineer in charge of the work	Cum	750	Rupees Seven hundred fifty only
7	66	Hire charge of pumping water 3.5 KL/hr capacity Pump etc complete as per specifications and directions of engineer in charge of the work	Hr	50	Rupees fifty only
8	165	Engaging unskilled heavy Mazdoor laboru for Guarding and for helping the public to immersion tank Ganesh Idols and to safe guard the public during the pooja Time etc complete as per specifications and directions of engineer in charge of the work	Days	245	Rupees Two Hundred forty five only
9	480	Providing erecting removing casurinapole barricading using poles of 7.50 to 10 cms, dia and 1.5 height above ground fixed vertically at intervals of 2.0 to 2.5 mtrs. C/C an horizontally at 0.50 mtr, above ground level, including fixing poles in the ground level for minimum depth of 3.0 mtr and tied with coir rope firmly including cost and conveyance of all materials, labour, lead and lift charges and complete on hire basis as per the engineer in charge	Mtrs	65	Rupees Sixty five only

	Approved Qty.	Description	Unit	Negotiation Tender Rates of R CHIDANANDA	
				In Figures	In Words
10	13200	Hire Charge for Shamiyana with Necessary Bambo Poles, Erection Charges Including transportation - (Size: 40ft x 30ft = 1200 sqft) etc complete as per specifications and directions of engineer in charge of the work	Sft	9.75	Rupees nine point Seventy five only
11	165	Hire Charges for Shamiyana Side Wall of 8ft Hight (Size: 10x 15ft = 150 Rft) etc complete as per specifications and directions of engineer in charge of the work	Rft	17	Rupees Seventeen only
12	220	Hire Charge for Armless Plastic Chairs etc complete as per specifications and directions of engineer in charge of the work	Nos	4	Rupees four only
13	110	Hire Charge for Wooden Table of Size 6ft x 2ft etc complete as per specifications and directions of engineer in charge of the work	Nos	40	Rupees forty only
14	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathe daluminium wire etc complete as per specifications and directions of engineer in charge of the work	Mtrs	9	Rupees nine only
15	66	Hire charge of 100 KVA Generator including operator, Fuel, transportation and Handling charges etc complete as per specifications and directions of engineer in charge of the work	Hr	562	Rupees five hundred Sixty Two
16	88	Hire chargesfor Flood lighting arrangements for the stage and existing immersion Tank during night time etc complete as per specifications and directions of engineer in charge of the work	Nos	285	Rupees Two Hundred Eighty five only
17	10	Hire charges compoment name 1087 Crane charges etc complete as per specifications and directions of engineer in charge of the work	Day	4000	Rupees four thousand only
18	357.5	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Cum	75	Rupees Seventy five only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

28/7

ರವರಿಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92.

ಮಾನ್ಯರೇ,

ವಿಷಯ:- Earthwork and other Works for Temporary Immersion Tank for Lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB Overhead Tank in Ward No. 9, Vidyaranyapura Sub Division. (for 2016-17 year) ಧರಸಂದಾನ ನಡೆಸುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖ:- ತಮ್ಮ ಕಛೇರಿ ಪತ್ರದ ಸಂಖ್ಯೆ:ಬೃ.ಬೆ.ಮ.ಪಾ/ಬ್ಯಾ.ವಿ/ಕಾ.ಅ/ /2016-17
ದಿನಾಂಕ:22.01.2016.

****

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂದಿಸಿದಂತೆ, ಇ-ಪ್ರಕ್ಯೂರ್‌ಮೆಂಟ್ ಟೆಂಡರ್ ಸಂಖ್ಯೆ **03/15-16, ದಿ:22.01.2016**ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: **17193** ಕ್ಕೆ ನನ್ನ ಧರಗಳನ್ನು ನಮೂದಿಸಿ ನಿಯಮಾನುಸಾರ ಟೆಂಡರ್ ಸಲ್ಲಿಸುರುತ್ತೇನೆ, ಉಲ್ಲೇಖ ಪತ್ರದಲ್ಲಿ ಎಲ್-1 ಗುತ್ತಿಗೆದಾರರಾದ ನನ್ನನ್ನು ಕಾಮಗಾರಿ ನಿರ್ವಹಿಸಲು ಧರಸಂದಾನ ನಡೆಸಲು ಕೋರಲಾಗಿರುತ್ತದೆ. ನಾನು ಸದರಿ ಕಾಮಗಾರಿಗೆ +4.93% ದರಗಳಿಗೆ ದರಸಂದಾನಕ್ಕೆ ಒಪ್ಪಿರುತ್ತೇನೆ.

ತಮ್ಮ ವಿಶ್ವಾಸಿ

28-7-2016

28/7
Exe. Engr.
Btp. Dn.

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಯಲಹಂಕ ವಲಯ ಬೆಂಗಳೂರು-92.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಕಛೇರಿ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು-92.

ದೂರವಾಣಿ: 23636671

ಸಂಖ್ಯೆ: ಬೃ.ಬೆ.ಮ.ಪಾ/ಬ್ಯಾ.ವಿ/ಕಾ.ಅ/J-03/2016-17 ದಿನಾಂಕ: 27/07/2016
18483

ರವರಿಗೆ,

R. Chidananda,
#15, MR nilaya
2nd cross, 3rd main
Durga layout
Vidyaranyapura
Bangalore-97.

ಮಾನ್ಯರೇ,

ವಿಷಯ:-Earthwork and other Works for Temporary Immersion Tank for Lord Ganesh Idols at Thindlu Vidyaranyapura Main Road near BWSSB Overhead Tank in Ward No. 9, Vidyaranyapura Sub Division. (for 2016-17 year) ಕಾಮಗಾರಿಗೆ ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುವ ಬಗ್ಗೆ.

ಗುತ್ತಿಗೆದಾರರಾದ ತಾವು ಇ-ಪ್ರಕ್ಯೂರ್‌ಮೆಂಟ್ ಟೆಂಡರ್ ಸಂಖ್ಯೆ: **03/15-16,** ದಿ:**22.01.2016**ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: **18483** ಭಾಗವಹಿಸಿದ್ದು, ನೀವು ಎಲ್-1 ಗುತ್ತಿಗೆದಾರರಾಗಿರುತ್ತೀರಿ. ಆದ್ದರಿಂದ ಸದರಿ ಕಾಮಗಾರಿಯನ್ನು ನಿರ್ವಹಿಸಲು ತಮ್ಮನ್ನು ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುತ್ತಾ, ಈ ಪತ್ರ ತಲುಪಿದ 3 ದಿನಗಳೊಳಗಾಗಿ ದರಸಂದಾನ ದರಗಳನ್ನು ಸಲ್ಲಿಸಲು ಸೂಚಿಸಿದೆ. ಇಲ್ಲವಾದಲ್ಲಿ ನಿಮ್ಮ ಟೆಂಡರ್‌ನ್ನು ರದ್ದುಪಡಿಸಿ ಮರುಟೆಂಡರ್ ಕರೆಯಲಾಗುವುದು ಈ ಬಗ್ಗೆ ಇನ್ನು ಮುಂದೆ ಯಾವುದೇ ತಿಳುವಳಿಕೆ ಪತ್ರಗಳನ್ನು ನೀಡಲಾಗುವುದಿಲ್ಲ.

Chidananda

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು 27/7
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು-92.

27/07